

## Discharge Ground Bus Component Sheet

|                        |                     |
|------------------------|---------------------|
| <b>GBE Catalog No.</b> | <b>DG 3B-36W-5L</b> |
| <b>Description</b>     | <b>3 Bay, 7500A</b> |
| <b>Tyco Comcode</b>    | <b>408528780</b>    |

| <b>Description</b>          | <b>Qty</b> | <b>Bolt Size</b> | <b>Length</b> | <b>FW</b> | <b>LW</b> | <b>Nut</b> | <b>Torque</b> |
|-----------------------------|------------|------------------|---------------|-----------|-----------|------------|---------------|
| 2 5/8" Insulator Bolt       | 8          | 5/8-11           | 2 1/4"        | 8         | 8         | N/A        | 48 ft/lbs.    |
| Link Plate Bolts            | 0          | 1/2-13           | 0             | 0         | 0         | 0          | 55 ft/lbs.    |
| Center Insulator Link Bolt  | 0          | 1/2-13           | 0             | 0         | 0         | 0          | 48 ft/lbs.    |
| 2 5/8" Insulators           | 8          | 5/8-11           | N/A           | N/A       | N/A       | N/A        | N/A           |
| Discharge Ground Busbars    | 5          |                  |               |           |           |            |               |
| 1/4" x 6" x 9" Link Plates  | 0          |                  |               |           |           |            |               |
| 1/4" x 6" x 9" Link Spacers | 0          |                  |               |           |           |            |               |