

Discharge Ground Bus Component Sheet

| | |
|------------------------|-----------------------|
| GBE Catalog No. | DG 3B-26W-7L |
| Description | 3 Bay, 10,000A |
| Tyco Comcode | 408528590 |

| Description | Qty | Bolt Size | Length | FW | LW | Nut | Torque |
|-----------------------------|------------|------------------|---------------|-----------|-----------|------------|---------------|
| 2 5/8" Insulator Bolt | 8 | 5/8-11 | 2 3/4" | 8 | 8 | N/A | 48 ft/lbs. |
| Link Plate Bolts | 0 | 1/2-13 | 0 | 0 | 0 | 0 | 55 ft/lbs. |
| Center Insulator Link Bolt | 0 | 1/2-13 | 0 | 0 | 0 | 0 | 48 ft/lbs. |
| 2 5/8" Insulators | 8 | 5/8-11 | N/A | N/A | N/A | N/A | N/A |
| Discharge Ground Busbars | 7 | | | | | | |
| 1/4" x 6" x 9" Link Plates | 0 | | | | | | |
| 1/4" x 6" x 9" Link Spacers | 0 | | | | | | |